# BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

**Executive Engineeer**
**Byatarayanapura Division**
**B.B.M.P., Bangalore - 92**

## DRAFT TENDER SCHEDULE

**Issued to :** **Original / Duplicate**

**Name of the Work : Improvements to Roads and Drains at Rachenahalli Main Road near Thanisandra Govt School in Ward No. 06, Thanisandra Village Limits.**

| Sl. No. | Quantity. | Description | Unit | Rates | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 1 | 617.18 | Earth work excavation by manual means in Hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work | Cum | 90.72 | |
| 2 | 1053.00 | Removing B.S. Slab Drain and stacking etc complete as per specifications and directions of engineer in charge of the work | Sqm | 50.11 | |
| 3 | 1053.00 | Refixing stone slabs of drains and pointing in CM (1:3) etc complete as per specifications and directions of engineer in charge of the work | Sqm | 70.04 | |
| 4 | 3920.00 | Scarifying existing stone metal layer upto 75mm thick along with their bituminous surface, picking up scarified materials and stacking of old serviceable materials with lead of 100m, sequential spreading of the salvaged aggregates with fresh aggregates on prepared base and consolidating as per water bound macadam specifications including cost of all labour, HOM of machineries etc complete as per specifications and directions of engineer in charge of the work | Sqm | 72.79 | |
| 5 | 784.00 | Providing, laying, spreading and compacting graded stone aggregate to **wet mix macadam** specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density etc complete as per specifications and directions of engineer in charge of the work | Cum | 1121.04 | |
| 6 | 3920.00 | Cleaning the existing WBM road surface including removing of binding materials and other foreign matter with wire bushes and small picks, sweeping with brooms or soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries, curing etc complete as per specifications and directions of engineer in charge of the work | Sqm | 10.53 | |

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

| Sl. No | Quantity. | Description | Unit | Rates | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 7 | 3920.00 | Providing and applying primer coat from 12.2 to 14.6kg per 10 sqm for surfaces of high porosity over prepared surface of granular base with cut back M.C.-70 or any other bitumen mixed with diesel at 13 kg per 10 sqm heated in bitumen boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries etc complete as per specifications and directions of engineer in charge of the work | Sqm | 142.07 | |
| 8 | 98.00 | Providing and laying semi dense bituminous concrete 25mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications clause No. 500.8 complete in all respects as per specificationsWith 60/70 grade bitumen using 40-60 HMP, etc complete as per specifications and directions of engineer in charge of the work | Cum | 9981.36 | |
| 9 | 617.18 | Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading etc complete as per specifications and directions of engineer in charge of the work | Cum | 72.71 | |

Signture of the Contractor

Assistant Executive Engineer
Byatarayanapura Sub-division
KRIDL BBMP, Bangalore

ಕರಡು ಟೆಂಡರ್ ಪಡ್ಯೆಲ್‌ನ್ನು
ತಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ.....( )
ತಿದ್ದುಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಿಲಾಗಿದೆ

CE Yelahanka

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92